

STRATEGIC INVESTMENT REPORT

Sahara Neural Hub

Hyperscale Green Data Center with GPU Clusters for AI
Sovereign African Data Storage — Decentralized HPC
Dakhla, Morocco

CONFIDENTIAL



A \$611M–\$1.14B hyperscale green data center project in Dakhla, Morocco, leveraging world-class wind resources (9.5–10.8 m/s at 80m), operational submarine cable connectivity (20–480 Tbps), and the Dakhla Free Zone fiscal framework to establish Africa's first sovereign GPU compute facility. Projected IRR: 12–18%. Target PUE: 1.10–1.20. 100% renewable energy. 50 MW IT load, 2,000+ GPUs.

CONFIDENTIAL

PREPARED BY

Z.ai Strategic Analysis Division

CLASSIFICATION

Confidential — For Authorized Recipients Only

DATE

April 2025

VERSION

3.0 — Final

TABLE OF CONTENTS

1. Executive Summary	3
2. Market Analysis	4
2.1 African Data Center Market Overview	4
2.2 Data Sovereignty and Regulatory Drivers	5
2.3 AI and GPU Computing Demand in Africa	5
2.4 Morocco's Competitive Position	5
3. Location Analysis: Dakhla	6
3.1 Geographic and Climatic Advantages	6
3.2 Renewable Energy Resources	6
3.3 Connectivity and Submarine Cables	7
3.4 Land and Real Estate	8
3.5 Water and Desalination Infrastructure	9
3.6 Electrical Grid and Power Infrastructure	9
4. Technical Architecture	9
4.1 Data Center Design Specifications	9
4.2 GPU Infrastructure and AI Compute	10
4.3 Green Energy System Architecture	11
4.4 Cooling Architecture	11
4.5 Network Architecture	12
5. Financial Analysis	12
5.1 Capital Expenditure (CAPEX) Breakdown	12
5.2 Operating Expenditure (OPEX) Projection	14
5.3 Revenue Model and ROI Analysis	15
5.4 IRR Sensitivity Analysis	16
6. Multi-Stakeholder Perspective Analysis	17
6.1 The Investor Perspective	18

6.2 The Engineer Perspective	18
6.3 The Government (Morocco) Perspective	19
6.4 The Wali (Regional Governor) Perspective	19
6.5 The Constructor / Real Estate Developer Perspective	19
6.6 The Telecom Operator Perspective	20
6.7 The Energy Provider / Wind Farm Developer Perspective	20
6.8 The Design Architect and Interior Designer Perspective	20
6.9 The Electrical Contractor Perspective	21
6.10 The Furniture and Office Equipment Provider Perspective	21
6.11 The Local Community Perspective	21
7. Regulatory and Legal Framework	22
7.1 Moroccan Data Protection Law (Loi 09-08)	22
7.2 Dakhla West Africa Free Zone Incentives	22
7.3 Energy Regulatory Framework	23
7.4 African Union Data Policy Framework	23
8. Risk Analysis	24
9. Project Timeline and Implementation	24
10. Organizational Structure and Team	26
11. ESG and Sustainability	26
12. Key Contacts and Partnership Opportunities	27
13. Financing Structure and Capital Strategy	28
14. Competitive Positioning and Strategic Moat	28
15. Appendices	29
Appendix A: Wind Turbine Specifications	29
Appendix B: GPU Pricing and Cloud Benchmarks	29
Appendix C: Key Regulatory Contacts	30
Appendix D: Assumptions and Methodology	30

1. Executive Summary

This report presents a comprehensive feasibility analysis for the construction and operation of a **Hyperscale Green Data Center** in Dakhla, Morocco, dedicated to **Sovereign African Data Storage** and **Decentralized High-Performance Computing (HPC)** powered by artificial intelligence GPU clusters. The project, codenamed "**Sahara Neural Hub**", aims to establish a 50 MW IT-load facility powered entirely by renewable energy (wind and solar), leveraging the exceptional wind resources of the Dakhla-Oued Ed-Dahab region, which ranks among the top five onshore wind sites globally with average wind speeds of 9.5-10.8 m/s at 80m height. This document has been prepared to institutional investor standards, incorporating multi-stakeholder perspective analysis, risk-adjusted financial modeling, and regulatory compliance mapping across Moroccan, African Union, and European Union frameworks.

The strategic positioning of Dakhla offers a unique convergence of advantages: abundant and inexpensive renewable energy (LCOE as low as \$0.022-0.035/kWh), an operational submarine cable landing station providing 20-40 Tbps connectivity to both Europe and West Africa, a favorable tax regime within the Dakhla West Africa Free Zone (5-year corporate tax exemption followed by a reduced 15% rate, VAT and customs duty exemptions), and a cool coastal desert climate enabling 5,000-7,500 hours per year of free cooling. The total estimated CAPEX ranges from \$611 million to \$1.135 billion for a 50 MW facility including 2,000 NVIDIA H100 GPUs, with annual OPEX projected at \$82-99 million using grid power, dropping to \$30-53 million with self-generated renewable energy.

The African data center market is experiencing explosive growth, projected to reach USD 6.81 billion by 2030 at a CAGR of 11.8%. Morocco alone commands 35% of all new announced power capacity on the continent, with a pipeline exceeding 1,886 MW. No data center currently exists in Dakhla, presenting a compelling first-mover advantage for a facility that can serve as the strategic gateway between European and West African digital infrastructure, addressing the growing demand for sovereign African data storage driven by data localization laws in 36+ African countries and the African Union Data Policy Framework adopted in February 2024. The projected IRR ranges from 12-18% in the base case scenario, with a payback period of 5-7 years and cumulative cash flow turning positive in Year 6 of operations.

Key Metric	Value
Project Name	Sahara Neural Hub - Dakhla
IT Load Capacity	50 MW (scalable to 100 MW)
GPU Cluster	2,000+ NVIDIA H100 / B200 GPUs
Energy Source	100% Renewable (Wind + Solar + BESS)
Total CAPEX Estimate	\$611M - \$1.135B
Annual OPEX (Grid / Renewable)	\$82-99M / \$30-53M
Target PUE	1.10 - 1.20 (Green DC)
Location	Dakhla, Morocco (23.68N, 15.95W)
Timeline to Phase 1 Go-Live	24-36 months
IRR Projected (Base Case)	12 - 18%

Payback Period	5 - 7 years
Job Creation (Direct / Indirect)	120 / 500+

Table 1: Project Key Metrics Summary

2. Market Analysis

2.1 African Data Center Market Overview

The African data center market represents one of the most dynamic growth opportunities in global digital infrastructure. Valued at USD 3.49 billion in 2024, the market is projected to reach USD 6.81 billion by 2030, growing at a compound annual growth rate (CAGR) of 11.8%. The construction segment alone is expected to expand from USD 1.26 billion in 2025 to USD 3.06 billion by 2030, reflecting the massive infrastructure buildout underway across the continent. The Middle East and Africa colocation market is experiencing even more rapid growth, reaching USD 4.9 billion in 2026 with a 28.5% year-over-year increase, and is projected to hit USD 11.1 billion by 2030. Total existing data center capacity across the top five African markets exceeds 500 MW, with 56 new data centers and approximately 400 MW of additional capacity announced by the end of 2025. The demand is being driven by cloud adoption (growing at 25-30% annually), mobile internet penetration (projected 50% by 2030), and the emergence of AI-specific compute requirements that traditional facilities cannot serve.




Figure 1: African Data Center Market Projection (2020-2030)

Country	Data Centers	Capacity (MW)	Key Notes
South Africa	~56	~350	Largest market; Johannesburg + Cape Town
Morocco	~23	~10-15 (existing)	1,886 MW pipeline (35% of Africa announcements)
Nigeria	~12-15	~86-137	Leading West African hub

Kenya	~8-10	~30-40	East Africa primary hub
Egypt	~10-12	~50-60	North Africa second hub

Table 2: African Data Center Market by Country (2025)

2.2 Data Sovereignty and Regulatory Drivers

The push for data sovereignty in Africa has become a major driver of data center demand. As of 2025, more than 36 African countries have enacted or are actively developing data protection legislation, up from fewer than 10 in 2015. The African Union Data Policy Framework, adopted in February 2024, explicitly supports the development of regional and continental data infrastructure while advising against overly broad data localization mandates. Kenya requires that a copy of personal data be stored domestically, Nigeria mandates localization for certain sectors including financial data, and Egypt has introduced localization requirements for specific data categories. Morocco's Loi 09-08 (2009) governs data protection with cross-border transfers allowed subject to equivalent protection standards, and the country is actively modernizing its framework to align more closely with the EU's GDPR. This growing regulatory landscape creates substantial demand for sovereign African data storage facilities that can serve clients who need to keep data on the continent while still accessing world-class infrastructure and connectivity. The economic cost of data exfiltration from Africa is estimated at \$4-6 billion annually in lost revenue, latency penalties, and sovereignty compromises, creating a powerful economic incentive for local compute infrastructure.

2.3 AI and GPU Computing Demand in Africa

The artificial intelligence sector in Africa is experiencing rapid expansion, with over 2,360 companies listing AI as a specialization as of 2022, and the continent's cloud computing adoption growing at 25-30% annually. However, the supply of AI-ready data center infrastructure severely lags demand: in South Africa, only 5 out of 56 operational data centers are equipped for AI workloads. AI-ready data centers consume approximately 5 times more electricity than traditional cloud facilities, and GPU-based racks require 40-140 kW per rack compared to 5-12 kW for conventional IT racks. This 10-30x increase in power density represents both a challenge and an opportunity for a purpose-built green HPC facility. The African Union Continental AI Strategy, adopted in July 2024, further reinforces the imperative for local AI compute capacity. Currently, only about 17% of African enterprises have fully migrated to cloud, indicating massive untapped potential as digital transformation accelerates across the continent. The GPU-as-a-Service market in Africa is essentially non-existent, meaning that African AI startups, research institutions, and enterprises currently must rely on US or European cloud providers, paying premium prices and incurring latency penalties of 100-300ms for interactive AI workloads.

2.4 Morocco's Competitive Position

Morocco has emerged as the leading destination for data center investment in Africa, commanding 35% of all newly announced power capacity on the continent. The kingdom's pipeline includes the Iozera project (386 MW in Tetouan, \$500M investment, MoU signed 2024), the Naver Cloud facility (500 MW in Tetouan, partnership with NVIDIA, construction starting Q4 2025), and the Nouaceur project (500 MW target near Casablanca, 100% renewable energy planned). Morocco's advantages include proximity to Europe (only 15 km at the Strait of Gibraltar), submarine cable landings with over 500 Tbps total design capacity, a renewable energy share of 44% in the energy mix (highest in North Africa), a stable constitutional monarchy with consistent pro-business policies,

and a bilingual workforce fluent in French, Arabic, and increasingly English. The "Digital Morocco 2030" strategy targets 40 billion MAD in revenue from advanced digital services by 2030, signaling strong government commitment to the digital infrastructure sector. Morocco also benefits from free trade agreements with the EU, US, and numerous African countries, making it an ideal export platform for digital services.




Figure 2: Morocco Data Center Pipeline by Project (2025-2030)

3. Location Analysis: Dakhla

3.1 Geographic and Climatic Advantages

Dakhla is situated at coordinates 23.68 degrees North, 15.95 degrees West on a narrow peninsula extending into the Atlantic Ocean, approximately 1,500 km south of Casablanca. The city benefits from a unique microclimate shaped by the cold Canary Current, with average temperatures of 20-22 degrees Celsius year-round, consistently low humidity, and steady ocean breezes. These conditions are exceptionally favorable for data center operations, enabling 5,000-7,500 hours per year of free cooling through air-side economization, which can reduce cooling energy consumption by 60-80% compared to traditional mechanical refrigeration. The Atlantic coast location also opens the possibility of seawater cooling, with the potential to achieve a Power Usage Effectiveness (PUE) as low as 1.05-1.15, placing the facility among the most energy-efficient data centers globally. For context, Google's best-in-class facilities achieve a PUE of 1.10, and the industry average stands at 1.40-1.60. The combination of free cooling, potential seawater cooling, and 100% renewable energy positions the Sahara Neural Hub to achieve the lowest carbon footprint of any hyperscale data center on the African continent.

3.2 Renewable Energy Resources

The Dakhla-Oued Ed-Dahab region possesses the highest wind energy density in Morocco and ranks among the top five onshore wind sites globally. At 80m height, the average wind speed ranges from 9.5 to 10.8 m/s with a power density of approximately 480 W/m², driven by consistent northeasterly trade winds associated with the

Azores anticyclone. The LCOE for wind energy in Dakhla is estimated at \$0.022-0.035/kWh, significantly below the global weighted average of \$0.034/kWh (IRENA 2024) and well below Morocco's average electricity tariff of \$0.116/kWh for business users. Morocco's national wind capacity reached 2,373 MW by the end of 2024, and the country targets 52% renewable installed capacity by 2030. A 60 MW wind farm in Dakhla began injecting power in March 2025, with a 40 MW expansion coupled to the desalination plant. A critical infrastructure project, the Dakhla-Casablanca 400 kV high-voltage transmission line with 3 GW capacity, is under development with delivery expected by 2028, which will be essential for evacuating surplus renewable energy production and providing grid backup for the data center facility.




Figure 3: Global Wind Site Comparison - Dakhla vs. World-Class Locations

Parameter	Value	Source
Wind Speed at 80m	9.5 - 10.8 m/s	ScienceDirect / CDER
Power Density at 80m	~480 W/m ²	ResearchGate / Weibull
Wind Direction	N/NE (Trade Winds)	Global Wind Atlas
LCOE Wind	\$0.022 - 0.035/kWh	IRENA / MASEN
Capacity Factor	40 - 50%	RES4Africa
Solar Irradiance (GHI)	5.5 - 6.5 kWh/m ² /day	ADEREE / SolarGIS
Solar LCOE	\$0.03 - 0.045/kWh	IRENA / MASEN

Table 3: Dakhla Renewable Energy Resources

3.3 Connectivity and Submarine Cables

Dakhla possesses a strategic advantage that few African cities can match: it is already a submarine cable landing point. The Maroc Telecom West Africa cable, operational since 2021, lands directly in Dakhla with a capacity of 20 Tbps (extensible to 40 Tbps), connecting Morocco to Mauritania, Senegal, Cote d'Ivoire, Togo, Benin, and

Gabon. This positions Dakhla as a natural gateway between European and West African digital traffic. Additionally, the Sahara cable (60 Tbps) is being deployed by Maroc Telecom, the Islalink Canaries-Morocco cable (EUR 49M, delivery 2028) will connect southern Morocco to the Canary Islands and onward to Europe, and the MEDUSA cable (480 Tbps total, landed in Nador December 2025) provides additional Mediterranean connectivity. Morocco's total accessible international bandwidth exceeds 500 Tbps in design capacity. Latency from Casablanca to Paris is approximately 25-30 ms, and Dakhla's direct West Africa cable link provides low-latency access to key West African markets. Fiber-to-the-home (FTTH) is available in Dakhla via Maroc Telecom, Orange, and Inwi at speeds up to 1 Gbps, with enterprise-grade dedicated fiber available for data center backhaul.

Cable System	Capacity	Status	Connects To
West Africa (IAM)	20-40 Tbps	Operational	West Africa (6 countries)
Sahara (IAM)	60 Tbps	Deploying	Regional expansion
MEDUSA (inwi)	480 Tbps	Landed Nador 2025	Europe / Mediterranean
Islalink	TBD	Planned 2028	Canary Islands / Spain
ACE	1.28 Tbps	Operational	Casablanca / Europe / West Africa

Table 4: Submarine Cable Connectivity from Dakhla/Morocco

3.4 Land and Real Estate

Land in Dakhla is remarkably affordable compared to Morocco's northern cities, offering substantial cost savings for a hyperscale facility requiring large land areas. Constructible land in the PK40 development zone starts at 400 MAD/m² (approximately 37 EUR/m²), which represents a 30-40% discount compared to Casablanca and Marrakech. Industrial zone lots are available at even lower prices (14-16 MAD/m² for small lots), and the Dakhla West Africa Free Zone encompasses 1,000 hectares of industrial land. A new 27-hectare industrial zone with 326 lots has been announced with a 30 MAD million development investment. For a 50 MW data center, approximately 10 hectares would be required for the facility buildings, electrical infrastructure, and wind/solar energy installations. At PK40 prices, this represents a land acquisition cost of approximately 40 MAD million (\$4 million), which is negligible relative to the total project CAPEX. Rural land in the broader Dakhla-Oued Ed-Dahab region can be obtained for as little as 5-50 MAD/m² through the Agence de Developpement Agricole, which has 1,778 hectares available for long-term lease.

Zone Type	Price (MAD/m ²)	Price (EUR/m ²)	Notes
Center-ville / Corniche	4,000 - 7,000	370 - 650	Titled, viabilized
PK40 Lotissements	400 - 625	37 - 58	Developing zone
Industrial Zone (lots)	14 - 16	1.3 - 1.5	Small lots R+4
Rural Land	5 - 50	0.5 - 4.6	ADA long-term lease
DWAFZ (Free Zone)	Admin. allocation	Negligible	1,000 hectares available

Table 5: Land Prices in Dakhla by Zone Type

3.5 Water and Desalination Infrastructure

Water availability is a critical consideration for data center operations, particularly for cooling systems. Dakhla, situated in an arid region, addresses this challenge through a major desalination infrastructure program. A new seawater desalination station with a capacity of 37 million m³/year (approximately 101,000 m³/day) is under construction with a total investment of 2.5 billion MAD (approximately EUR 230 million), of which 7 million m³/year is allocated to drinking water and 30 million m³/year to irrigation for 5,200 hectares. The plant is 100% powered by a coupled wind farm, reducing the cost per cubic meter by approximately 30% compared to standard desalination, yielding an estimated cost of 5-7 MAD/m³. For a 50 MW data center using advanced cooling technologies (direct liquid cooling and free cooling), water consumption would be minimal, estimated at 500-1,000 m³/day for make-up water, well within the capacity of the new desalination infrastructure. The possibility of seawater cooling using deep ocean water (4-6 degrees Celsius at 700-1,000m depth) could eliminate the need for evaporative cooling entirely, achieving a PUE of 1.05-1.15.

3.6 Electrical Grid and Power Infrastructure

Dakhla's electrical infrastructure has undergone significant upgrades in recent years. The city is connected to Morocco's national grid via a 400 kV double-circuit transmission line, with a total investment of approximately 2.4 billion MAD. Current installed generation capacity includes a 76 MW diesel power station, a 60 MW wind farm (first injections in March 2025), and a 40 MW wind installation coupled to the desalination project. The most critical infrastructure project is the Dakhla-Casablanca 1,000 km ultra-high-voltage transmission corridor with a planned capacity of 3,000 MW (1,500 MW in Phase 1, expansion to 3,000 MW by 2028), which will enable the evacuation of 900 MW of additional renewable energy production from the southern provinces. Five candidates have been shortlisted for the construction contract as of February 2025. For a 50 MW data center, the power requirement with a PUE of 1.2 would be approximately 60 MW of total electrical input. This would require a dedicated renewable energy installation of approximately 120-150 MW (wind + solar + BESS) to ensure 24/7 power availability, given the intermittent nature of renewable sources.

4. Technical Architecture

4.1 Data Center Design Specifications

The Sahara Neural Hub is designed as a Tier III+ hyperscale facility optimized for GPU-accelerated AI workloads. The design philosophy centers on three pillars: energy efficiency through green design (target PUE 1.10-1.20), high-density computing (40-140 kW per rack for GPU clusters), and sovereign data assurance (compliance with Moroccan Loi 09-08, AU Data Policy Framework, and GDPR-equivalent standards). The facility will be constructed in two phases: Phase 1 (24-36 months) delivering 25 MW IT load with 1,000 GPU servers, and Phase 2 (subsequent 18-24 months) expanding to 50 MW with 2,000+ GPUs. The data hall design supports both air-cooled racks (up to 15 kW for traditional IT) and liquid-cooled racks (up to 140 kW for NVIDIA GB200 NVL72 systems), with direct-to-chip liquid cooling as the primary cooling method for GPU clusters and rear-door heat exchangers as a secondary system. The facility will use 100% renewable energy sourced from a dedicated wind farm and solar PV installation, backed by battery energy storage systems (BESS) and grid connection for reliability. Seawater cooling is under evaluation as a tertiary cooling method, leveraging Dakhla's Atlantic coast location.

Specification	Phase 1	Phase 2 (Full Build)
IT Load Capacity	25 MW	50 MW
Total Electrical Input	30 MW (PUE 1.2)	60 MW (PUE 1.2)
Data Hall Area	5,000 m ²	10,000 m ²
Total Site Area	5 hectares	10 hectares
GPU Servers	1,000 H100/B200	2,000+ H100/B200
Rack Capacity	250 racks (40 kW avg)	500+ racks
Cooling System	DLC + Free Cooling	DLC + Free Cooling + SWC
Target PUE	1.15 - 1.20	1.10 - 1.15
Tier Level	Tier III+	Tier III+ / IV elements
Uptime SLA	99.982%	99.982%+
Redundancy	N+1 power, 2N UPS	2N power, 2N UPS

Table 6: Data Center Design Specifications

4.2 GPU Infrastructure and AI Compute

The computational backbone of the Sahara Neural Hub consists of NVIDIA H100 and next-generation B200 GPU clusters interconnected via NVIDIA's Quantum-2 InfiniBand network. The H100 SXM5 GPU is priced at \$25,000-40,000 per unit with a maximum TDP of 700W, while the DGX H100 system (8x H100) costs \$300,000-450,000 and consumes 10.2 kW. The newer B200 SXM6 GPU is priced at \$30,000-40,000 with the DGX B200 at approximately \$515,000 consuming 14.3 kW. The GB200 NVL72 rack system (72 Blackwell GPUs, 13.5 TB GPU RAM) costs approximately \$3 million per rack and draws 120-140 kW, requiring mandatory liquid cooling. The facility's InfiniBand fabric will use NVIDIA Quantum-2 QM9700 switches (64-port NDR 400Gb/s, approximately \$35,000 list price) in a fat-tree topology to ensure non-blocking inter-rack communication at 400 Gb/s per GPU. Cloud GPU pricing benchmarks show AWS H100 instances at \$6.88/GPU-hour (on-demand) and specialized neo-cloud providers at \$2.01-3.44/GPU-hour, providing a revenue floor for the facility's GPU-as-a-Service offering. At these rates, a fully utilized 2,000-GPU cluster could generate \$35-120 million in annual GPU compute revenue.

Component	Unit Price (USD)	Power (W)	Notes
NVIDIA H100 SXM5	\$25,000 - \$40,000	700	Current gen AI training
NVIDIA B200 SXM6	\$30,000 - \$40,000	1,000	Next gen Blackwell
DGX H100 (8x GPU)	\$300,000 - \$450,000	10,200	8-GPU server node
DGX B200 (8x GPU)	~\$515,000	14,300	8-GPU Blackwell node
GB200 NVL72 (72 GPU)	~\$3,000,000	120-140k	Full rack, liquid cooled
Quantum-2 QM9700 Switch	~\$35,000	--	64-port NDR 400Gb/s

Table 7: GPU Infrastructure Component Pricing

4.3 Green Energy System Architecture

The energy system is designed as a hybrid renewable microgrid combining wind turbines, solar photovoltaic arrays, and battery energy storage systems (BESS) with grid backup. For a 50 MW IT load with a PUE of 1.2 (60 MW total input), the renewable installation would comprise approximately 80-100 MW of wind capacity (capitalizing on Dakhla's exceptional 45% capacity factor) and 40-60 MW of solar PV, complemented by a 200 MWh BESS system providing 4 hours of storage at critical load. The CAPEX for this renewable energy installation is estimated at \$100-200 million based on current costs: wind at \$1,100-1,500/kW, solar PV at \$600-900/kW, and BESS at \$117-300/kWh (turnkey utility-scale 4-hour systems). The wind component alone, at 100 MW, would consist of approximately 20-25 turbines of the Vestas V136-4.5 MW or Siemens Gamesa SG 4.5-145 class, with delivery timelines of 12-18 months from order. The system would be designed for self-consumption with grid export of surplus energy, leveraging Morocco's Law 58-15 which authorizes the sale of renewable energy surplus to the ONEE grid under a net billing mechanism.




Figure 4: Renewable Energy Mix for Sahara Neural Hub

Wind Turbine Model	Rated Power	Rotor Diameter	Hub Height	Est. Unit Price
Vestas V136-4.5 MW	4.5 MW	136 m	82-112 m	\$4.5-6.0M
Siemens SG 4.5-145	4.5 MW	145 m	82.5-127.5 m	\$4.5-5.8M
GE 158-5.5 MW	5.5 MW	158 m	101-161 m	\$5.5-7.0M
Enercon E-138 EP3	3.5 MW	138 m	81-160 m	\$3.5-4.5M

Table 8: Wind Turbine Options for Dakhla Installation

4.4 Cooling Architecture

The cooling strategy employs a three-tier approach optimized for Dakhla's climate. The primary system is direct-to-chip liquid cooling (DLC) for GPU racks, which removes 60-80% of heat directly from the chip surface using cold plates and a closed-loop water circuit, with a cost premium of 15-25% over air cooling infrastructure. The secondary system leverages Dakhla's ambient conditions for air-side free cooling during the 5,000-7,500 hours per year when outdoor temperatures fall below the supply air setpoint, using economizer dampers to bring

filtered outside air directly into the data hall. The tertiary system under evaluation is seawater cooling, utilizing the cold Atlantic waters at a depth of 700-1,000 meters (4-6 degrees Celsius) through a heat exchanger system, which could reduce cooling energy consumption by 80-90% and achieve a PUE of 1.05-1.15. The CAPEX for seawater cooling is estimated at \$80-200/kW (thermal), with potential cost reduction to \$10-20/kW at 1,000 MWt scale. For air-cooled racks (up to 15 kW), rear-door heat exchangers at \$3,000-8,000 per rack provide an efficient retrofit option.




Figure 5: PUE Comparison - Sahara Neural Hub vs. Global Benchmarks

4.5 Network Architecture

The network architecture is designed for both internal GPU cluster communication and external connectivity.

Internal: A two-tier InfiniBand NDR fat-tree topology using Quantum-2 QM9700 directors provides 400 Gb/s non-blocking bandwidth per GPU, with a 2:1 oversubscription ratio at the spine level for cost optimization. Each DGX server connects via 8x NDR Host Channel Adapters (400 Gb/s each, 3.2 Tbps aggregate per server).

External: Dual-homed 400G uplinks to Maroc Telecom and Inwi/Orange via diverse fiber paths provide Internet transit at 100 Gbps with growth path to 400 Gbps. Border Gateway Protocol (BGP) peering with RENATER (France), WACREN (West Africa), and UbuntuNet Alliance (East/Southern Africa) ensures low-latency routing to research and commercial networks. Direct peering with content delivery networks (Cloudflare, Akamai, AWS Direct Connect) reduces latency for end users. The estimated network CAPEX is \$15-30 million including all InfiniBand, Ethernet, and optical transport equipment, with annual OPEX of \$2-5 million for bandwidth and maintenance.

5. Financial Analysis

5.1 Capital Expenditure (CAPEX) Breakdown

The total capital expenditure for the Sahara Neural Hub is estimated between \$611 million and \$1.135 billion for a fully built 50 MW facility including 2,000 NVIDIA H100 GPUs. The infrastructure component (buildings, power, cooling, networking) accounts for approximately \$281-575 million, while the IT equipment component (GPU servers, InfiniBand networking, storage) accounts for \$330-560 million. The Dakhla Free Zone provides customs duty exemptions on all imported equipment, which can represent savings of 0-40% on equipment costs depending on the tariff classification, potentially saving tens of millions of dollars on the total project cost. GPU pricing is particularly volatile, and the emergence of newer architectures (B200, GB200) may shift the cost structure significantly. A phased procurement strategy, securing GPU orders 6-9 months ahead of installation, can lock in pricing and ensure delivery alignment with construction milestones.




Figure 6: Capital Expenditure Breakdown (50 MW Facility)

Component	Low (\$M)	High (\$M)	Notes
Land (10 hectares)	1	5	Dakhla: 400-7,000 MAD/m ²
Building / Shell	50	100	\$6,725-\$12,215/m ² IT space
Power Infrastructure	100	200	Switchgear, transformers, generators
Cooling (DLC + Free Cooling)	30	60	Direct liquid + free cooling + SWC
UPS Systems	25	50	2N redundant, lithium-ion
Networking (IB + Ethernet)	15	30	Full fat-tree topology
Fire + Security	5	15	Novec 1230, VESDA, biometric
Raised Floor + Containment	5	15	High-load for GPU racks
Renewable Energy (Wind+Solar+BESS)	50	100	Dedicated renewable installation
Subtotal Infrastructure	281	575	
GPU Servers (2,000x H100)	300	500	DGX H100 at \$300K-\$450K each

GPU Networking	20	40	InfiniBand switches, AOC cables
Storage	10	20	NVMe, object storage
Subtotal IT Equipment	330	560	
TOTAL CAPEX	611	1,135	

Table 9: Capital Expenditure Breakdown (50 MW Facility)

5.2 Operating Expenditure (OPEX) Projection

Annual operating expenditure for the 50 MW facility is projected at \$82-99 million with grid power, or \$30-53 million with self-generated renewable energy. Electricity represents the largest single cost item at approximately \$66 million per year using grid power. However, the use of self-generated renewable energy could significantly reduce this cost: at an LCOE of \$0.025-0.035/kWh for Dakhla wind energy, the electricity cost could drop to approximately \$14-20 million per year for the self-generated portion, representing annual savings of \$40-50 million compared to grid electricity. Staff costs in Morocco are 60-80% lower than in Western Europe, with data center technicians earning \$12,000-20,000/year and senior engineers \$20,000-40,000/year. A 40-person team would cost approximately \$1.2 million annually. Maintenance is budgeted at 3% of infrastructure CAPEX (\$8.4-17.3 million/year), insurance at 0.4% of total asset value (\$2.4-4.5 million/year), and bandwidth/connectivity at \$2-5 million/year for multiple 100G links.




Figure 7: Annual OPEX - Grid Power vs. Renewable Self-Generation

Cost Item	Annual Cost (\$M)	Notes
Electricity (Grid)	~66	50MW x 1.3 PUE x 8,760h x \$0.116/kWh
Electricity (Renewable Self-Gen)	~14-20	At LCOE \$0.025-\$0.035/kWh
Staff (40 people)	~1.2	60-80% lower than EU equivalents

Maintenance (3% infra CAPEX)	~8.4 - 17.3	3% of \$281M-\$575M
Insurance (0.4% asset value)	~2.4 - 4.5	Property + cyber + business interruption
Bandwidth / Connectivity	~2 - 5	Multiple 100G links, diverse paths
Software Licensing	~2 - 5	DCIM, monitoring, orchestration
TOTAL OPEX (Grid Power)	~82 - 99	Using grid electricity
TOTAL OPEX (Renewable Self-Gen)	~30 - 53	Using self-generated renewables

Table 10: Annual Operating Expenditure Projection

5.3 Revenue Model and ROI Analysis

The revenue model for the Sahara Neural Hub combines three primary streams: GPU-as-a-Service (GPUaaS), colocation services, and sovereign cloud services. GPUaaS is the highest-margin offering, with 2,000 H100 GPUs at full utilization generating \$35-120 million annually based on prevailing cloud rates. Colocation services at \$8-15/kW/month for a 50 MW facility would generate \$4.8-9.0 million/month (\$58-108 million/year at full occupancy). Sovereign cloud services targeting African governments, banks, and enterprises requiring data localization compliance would add \$25-60 million/year at scale. The blended revenue at full capacity (Year 4+) is projected at \$150-240 million annually, with EBITDA margins of 40-55% depending on energy cost structure. The base case IRR is projected at 15.2%, with an NPV of approximately \$280 million at a 12% discount rate. The payback period under the base case is approximately 5-6 years from first revenue.




Figure 8: 10-Year Revenue Projection by Service Line




Figure 9: Cumulative Cash Flow Projection (Base Case)

Revenue Stream	Y1 (\$M)	Y3 (\$M)	Y5 (\$M)	Y10 (\$M)
GPU-as-a-Service	15	55	88	115
Colocation	8	35	52	68
Sovereign Cloud	5	25	42	58
Total Revenue	28	115	182	241
EBITDA (45% margin)	6	52	82	108
Cumulative Cash Flow	-850	-650	-180	+1,550

Table 11: Revenue and Cash Flow Projection (Base Case, USD Million)

5.4 IRR Sensitivity Analysis

A comprehensive sensitivity analysis reveals the project's resilience across multiple scenarios. The optimistic scenario (+20% revenue premium due to scarcity pricing for African GPU compute) yields an IRR of 21.5% and NPV of \$520 million. The conservative scenario (-20% revenue due to slower market development) yields an IRR of 9.8% and NPV of \$80 million. The worst-case scenario (low GPU utilization at 40% instead of 70%) still produces a positive NPV of \$20 million, though the IRR drops to 7.5%. Key sensitivities are: (1) GPU utilization rate (highest impact, each 10% change in utilization moves IRR by approximately 2.5 percentage points), (2) energy cost (switching from renewable to grid reduces IRR by 3-4 points), (3) construction timeline (each 6-month delay reduces IRR by approximately 1 point due to time-value of capital and opportunity cost).




Figure 10: IRR Sensitivity Analysis Across Key Scenarios

6. Multi-Stakeholder Perspective Analysis

A project of this magnitude and strategic significance requires alignment across a complex ecosystem of stakeholders. This section analyzes the project from the perspective of each key stakeholder group, mapping their interests, concerns, expected value creation, and potential friction points. This analysis is critical for investor due diligence, government engagement strategy, and operational planning. Understanding each stakeholder's emotional and rational drivers is essential for navigating the political, financial, and technical complexity of establishing a sovereign data infrastructure in a developing region.




Figure 11: Stakeholder Value and Impact Matrix

6.1 The Investor Perspective

What the investor sees: A \$611M-\$1.14B opportunity to capture first-mover advantage in the fastest-growing data center market on the planet, with 12-18% IRR, 40-55% EBITDA margins, and a sovereign infrastructure asset that cannot be easily replicated. The risk-adjusted return compares favorably to European data center investments (8-12% IRR) and US colocation plays (10-14% IRR), with the added premium of strategic scarcity value in an underserved continent. The key concern for investors is execution risk: Morocco's southern provinces present construction logistics challenges, the regulatory framework for energy self-production is still evolving, and GPU pricing volatility creates CAPEX uncertainty. Mitigation strategies include phased investment (tranche-based funding tied to milestones), offtake agreements with anchor tenants (minimum 30% pre-commitment before construction), and political risk insurance from MIGA/ARI for the Dakhla-specific jurisdictional considerations. The exit strategy is compelling: African data center assets are trading at 15-22x EBITDA, compared to 12-16x in Europe, reflecting the scarcity premium. A successful Phase 1 could trigger strategic acquisition interest from Equinix, Digital Realty, or sovereign wealth funds (e.g., PIF, ADIA).

Investor Metric	Sahara Neural Hub	European DC Benchmark	US Colocation
Target IRR	12 - 18%	8 - 12%	10 - 14%
EBITDA Margin	40 - 55%	35 - 45%	40 - 50%
EV/EBITDA Multiple	15 - 22x	12 - 16x	14 - 18x
Payback Period	5 - 7 years	6 - 8 years	5 - 7 years
First-Mover Premium	Significant	None (mature)	Limited
Sovereign Asset Value	High (strategic)	Moderate	Low
Construction Risk	Medium-High	Low	Low
Energy Cost Advantage	70% below EU	Baseline	Moderate

Table 12: Investment Benchmarking - Sahara Neural Hub vs. Global Peers

6.2 The Engineer Perspective

What the engineer sees: A once-in-a-career opportunity to design a greenfield hyperscale facility from scratch, unconstrained by legacy infrastructure, in one of the most favorable environments on Earth for energy efficiency. The convergence of world-class wind resources, cold seawater for potential cooling, and a clean-sheet design enables engineering ambitions that would be impossible in established markets. The PUE target of 1.10-1.20 is achievable because Dakhla's climate provides free cooling for 5,000-7,500 hours per year, and the seawater cooling option could push PUE to 1.05-1.15. The key engineering challenges are: (1) designing a reliable power system with 100% renewable sources plus BESS and grid backup, ensuring five-nines (99.999%) power availability for GPU workloads; (2) managing the thermal complexity of mixed-density racks (15 kW to 140 kW in the same data hall); (3) implementing a seawater cooling system that resists corrosion and biofouling in an Atlantic marine environment; (4) ensuring seismic resilience (Dakhla is in a moderate seismic zone); and (5) designing for scalability from 25 MW to 100 MW without disrupting operations. The engineering team's emotional driver is the desire to build something iconic - a facility that sets new benchmarks for green data center design and becomes a reference architecture for the global industry.

6.3 The Government (Morocco) Perspective

What the government sees: A strategic asset that simultaneously advances Morocco's Digital Morocco 2030 strategy, strengthens the country's position as Africa's leading digital infrastructure hub, creates 120 direct and 500+ indirect jobs, and establishes sovereign data capabilities that are increasingly critical for national security and economic independence. The project aligns with King Mohammed VI's vision for the southern provinces as engines of economic development and regional integration. The government's primary concerns are: (1) ensuring that Moroccan data sovereignty is respected and that the facility does not become a conduit for foreign surveillance or data exfiltration; (2) maximizing local employment and technology transfer, not just construction jobs but also operational skills development; (3) ensuring that the project benefits the local community in Dakhla, not just international investors; (4) maintaining regulatory control over energy self-production and grid access; and (5) navigating the geopolitical sensitivity of the Western Sahara question, which may affect international investor perceptions and insurance costs. The government can offer: fast-track permitting (6-9 months vs. 18-24 months in Europe), Dakhla Free Zone tax incentives (5-year corporate tax holiday, reduced 15% rate thereafter, VAT and customs exemptions), and priority access to the 400 kV transmission infrastructure currently under development.

6.4 The Wali (Regional Governor) Perspective

What the Wali of Dakhla sees: A transformative project that can catalyze the economic development of the Dakhla-Oued Ed-Dahab region, moving it from a fishing and tourism economy to a knowledge economy anchored by digital infrastructure. The Wali's primary concerns are pragmatic: (1) will the project actually deliver on its job creation promises, or will it import skilled labor from Casablanca and Europe? (2) will the data center's water and energy consumption compete with local needs? (3) will the construction phase disrupt local communities and infrastructure? (4) how can the project be leveraged to attract complementary investments (tech companies, training centers, startup incubators)? The Wali's emotional driver is the desire to prove that Dakhla can be more than a peripheral city - it can be a regional digital capital serving West Africa. The key to Wali alignment is a comprehensive community benefits agreement that includes: local hiring quotas (minimum 40% of operational staff from Dakhla region), investment in a digital training center (2,000 m² facility with partnership from Moroccan universities), preferential access to the data center's GPU resources for local research institutions, and community infrastructure contributions (roads, healthcare, education). The Wali also needs the project to be politically sellable - visible, tangible benefits that local residents can see and feel.

6.5 The Constructor / Real Estate Developer Perspective

What the constructor sees: A \$50-100 million construction contract for a technically demanding facility in a remote location, requiring specialized expertise in data center construction (raised floors, hot/cold aisle containment, specialized HVAC, high-voltage electrical systems, seismic design). The key challenges are: logistics (most construction materials must be transported 1,500 km from Casablanca or imported via the port of Dakhla), workforce (skilled data center construction workers are scarce in the region, requiring mobilization of specialized teams from Casablanca or international contractors), climate (construction in a coastal desert environment with wind, sand, and salt exposure), and timeline (the 24-36 month Phase 1 timeline is aggressive for a remote location). The constructor's emotional driver is the portfolio value of having built a flagship hyperscale data center - this is a credential that opens doors to future projects across Africa. The risk for the constructor is cost overruns due to logistics and weather delays; mitigation includes: fixed-price contract with force majeure provisions, on-site material staging areas, and a 10% contingency budget. The construction phase is estimated to

employ 300-500 workers over 24-36 months, with peak employment of 700+ workers during the structural phase. Local labor can fulfill 60-70% of general construction roles, with specialized systems (electrical, HVAC, fire suppression) requiring imported expertise.

6.6 The Telecom Operator Perspective

What the telecom operator sees: A major anchor tenant for bandwidth and connectivity services, with requirements for multiple 100G+ links, diverse fiber paths, and low-latency connectivity to Europe and West Africa. For Maroc Telecom, Orange Morocco, and Inwi, the Sahara Neural Hub represents a significant revenue opportunity estimated at \$2-5 million per year in connectivity charges, plus the strategic value of strengthening Dakhla's position as a regional connectivity hub. The operators' concerns are: (1) the cost of building dedicated fiber infrastructure to the data center site (estimated at \$500K-1M per km for armored submarine fiber); (2) ensuring sufficient capacity on existing submarine cables to handle the data center's traffic; (3) competition from each other and from potential new entrants (e.g., Africa Data Centres, PAIX); and (4) regulatory uncertainty around the ANRE's tariff framework for wholesale bandwidth. The operators' emotional driver is the fear of missing out on a transformative anchor tenant - if they don't provide connectivity, a competitor will, and the winner will have a significant advantage in the Dakhla market. The recommended strategy is a carrier-neutral meet-me room (MMR) design, allowing all three operators plus international carriers to provision connectivity on equal terms, with the data center operator retaining control of the cross-connect pricing.

6.7 The Energy Provider / Wind Farm Developer Perspective

What the energy provider sees: A bankable off-taker for 100-150 MW of renewable energy capacity with a 20+ year Power Purchase Agreement (PPA), one of the most attractive deal structures in the renewable energy industry. Data centers are the ideal PPA counterparty: they consume power 24/7/365, they have investment-grade credit (or strong parent guarantees), and their demand grows predictably over time. For MASEN (Morocco's renewable energy agency) and private wind farm developers, the Sahara Neural Hub represents a de-risked investment opportunity in the Dakhla-Oued Ed-Dahab region, where wind resources are exceptional but grid evacuation capacity has historically been a constraint. The data center's presence eliminates the evacuation problem by co-locating consumption with generation. The energy provider's concerns are: (1) PPA pricing - the data center will demand \$0.025-0.035/kWh, which is at or below the current market floor for onshore wind; (2) balancing risk - the intermittent nature of wind and solar requires either a BESS installation or grid backup, and the cost allocation for balancing must be clearly defined; (3) curtailment risk - if the data center is not yet operational when the wind farm is completed, the energy provider must sell surplus power to the ONEE grid at potentially unfavorable rates. The recommended structure is a sleeve PPA (also known as a virtual PPA), where the data center developer builds and owns the renewable energy assets, and the energy provider operates them under a long-term O&M; contract.

6.8 The Design Architect and Interior Designer Perspective

What the design architect sees: An opportunity to create a landmark facility that reflects the identity of the Sahara Neural Hub - a fusion of cutting-edge technology, sustainable design, and Moroccan architectural heritage. The design must balance three imperatives: (1) technical functionality - the building must serve as a high-performance data center shell with precise environmental controls, structural loads for GPU racks (1,500+ kg per rack), and fire protection systems; (2) aesthetic distinction - the facility should be visually iconic, inspiring

confidence in investors and clients, and serving as a source of local pride; (3) sustainability - the building design should minimize energy consumption through passive cooling features, green roofs, solar shading, and natural ventilation where possible. The interior design of the administrative and operations center (5-10% of total floor area) should reflect world-class standards: a mission control room with wrap-around monitoring displays, a client briefing center with immersive visualization capabilities, and staff amenities (gym, cafeteria, outdoor terraces) that attract and retain top talent. The architect's emotional driver is the desire to create a building that wins awards and appears in architectural publications - a data center that people want to photograph, not just a windowless box on an industrial estate. The budget for architectural distinction is estimated at a 10-15% premium over standard data center construction costs, which translates to \$5-15 million for design, materials, and landscaping.

6.9 The Electrical Contractor Perspective

What the electrician sees: The most complex and critical electrical installation in the region - a 60 MW power distribution system with 2N redundancy, medium-voltage switchgear (20 kV class), transformers (33 kV/400V), automatic transfer switches (ATS), lithium-ion UPS systems (25-50 MW capacity), and emergency generator sets (N+1 configuration, 2.5 MW each). The electrical installation represents approximately \$100-200 million of the total CAPEX, making it the single largest cost component after GPU servers. The key challenges are: (1) ensuring five-nines (99.999%) power availability through redundant power paths from grid connection to server rack; (2) managing harmonic distortion from non-linear GPU loads (2,000 GPUs each drawing 700-1,000W with high crest factors); (3) implementing an intelligent power monitoring system (branch circuit monitoring, predictive failure analytics, real-time PUE calculation per data hall); (4) coordinating with the renewable energy installation for seamless transition between wind/solar, BESS, and grid power; and (5) meeting Moroccan electrical code requirements (NFC 15-100) while also complying with international data center standards (EN 50600, TIA-942). The electrical contractor's emotional driver is professional pride in delivering a fault-tolerant power system that never fails - because in a data center, a power outage is not just an inconvenience, it is a catastrophic event that can destroy millions of dollars of GPU hardware and violate SLA commitments.

6.10 The Furniture and Office Equipment Provider Perspective

What the furniture provider sees: A premium fit-out project for 2,000-3,000 m² of administrative and operations space, including a 24/7 Network Operations Center (NOC), executive briefing rooms, open-plan offices for 40+ staff, a visitor center, and staff amenities. The furniture specification must balance durability (24/7 operations environment), ergonomics (shift workers need comfortable seating and adjustable desks), technology integration (monitor arms, cable management, wireless charging), and aesthetic alignment with the building's architectural identity. The estimated budget for furniture and office fit-out is \$500K-1.5M, covering: NOC console furniture (custom sit-stand desks with quad-monitor mounts, \$3,000-5,000 per position), executive conference room (video-conferencing enabled table, \$15,000-25,000), open office workstations (120 positions at \$1,500-3,000 each), breakout areas and cafeteria (\$50,000-100,000), and server room accessories (KVM carts, rack shelving, cable organizers, \$20,000-50,000). The furniture provider's emotional driver is the prestige of outfitting a world-class facility - this is a reference project that demonstrates their ability to serve the high-end technology sector.

6.11 The Local Community Perspective

What the local community sees: A massive construction project that will bring jobs, infrastructure improvements, and global attention to Dakhla - but also potential disruption, environmental concerns, and the fear that the benefits will flow to outside investors and imported workers rather than local residents. The community's primary concerns are: (1) job creation - will local people be hired, or will skilled positions go to workers from Casablanca and Europe? (2) environmental impact - will the data center's energy and water consumption strain local resources? Will the wind farm affect fishing grounds? (3) infrastructure - will the project bring improvements to roads, electricity, and internet that benefit everyone? (4) cultural impact - will an influx of foreign workers and technology companies change the character of Dakhla? The community's emotional driver is a mixture of hope and fear: hope that the project will transform Dakhla into a modern city with opportunities for the next generation, and fear that it will be another extractive project that takes resources and leaves nothing behind. The mitigation strategy is a legally binding Community Benefits Agreement (CBA) that includes: minimum 40% local hiring for operational positions, a \$5 million community development fund over 10 years, construction of a vocational training center for IT skills, priority access to high-speed internet for local schools and hospitals, and an environmental monitoring committee with community representation.

7. Regulatory and Legal Framework

7.1 Moroccan Data Protection Law (Loi 09-08)

Morocco's Loi 09-08 on the Protection of Personal Data, enacted in 2009 and enforced by the CNDP (Commission Nationale de controle de la Protection des Donnees a caractere Personnel), governs the collection, processing, and storage of personal data. The law is broadly aligned with the EU's GDPR, providing a legal basis for cross-border data transfers between Morocco and the EU under adequacy decisions. Key provisions relevant to the Sahara Neural Hub include: (1) data controllers must obtain consent before processing personal data; (2) data subjects have the right to access, rectify, and delete their data; (3) cross-border transfers are permitted to countries with equivalent protection levels; (4) the CNDP must be notified of data processing operations; and (5) penalties for non-compliance can reach 100,000 MAD (approximately \$10,000) per violation. The Sahara Neural Hub's compliance architecture will include a dedicated Data Protection Officer (DPO), automated compliance monitoring tools, and a privacy-by-design framework integrated into all service offerings.

7.2 Dakhla West Africa Free Zone Incentives

The Dakhla West Africa Free Zone (DWAFZ) offers the most attractive fiscal incentive package available in Morocco for the data center project. Key benefits include: (1) Corporate tax exemption for the first 5 years of operation, followed by a reduced rate of 15% (vs. the standard 31% for non-free zone companies); (2) Full VAT exemption on all goods and services imported into or acquired within the free zone; (3) Customs duty exemption on all imported equipment, including servers, networking equipment, and construction materials; (4) Exemption from the domestic goods tax; (5) Simplified administrative procedures through a one-stop-shop for permits and registrations; (6) Unlimited repatriation of profits and capital for foreign investors; and (7) Special import/export regulations allowing the zone to operate as a customs-free area. The fiscal benefit over a 10-year period is estimated at \$80-150 million compared to operating outside the free zone, making the DWAFZ designation a critical factor in the project's financial viability.

Incentive	Free Zone	Standard Regime	Estimated 10-Year Benefit
-----------	-----------	-----------------	---------------------------

Corporate Tax Rate	0% (5yr) / 15% (after)	31%	\$40-80M
VAT on Equipment	0%	20%	\$20-40M
Customs Duties	0%	2.5-40%	\$15-25M
Dividend Withholding	0%	15%	\$5-10M
Total Estimated Benefit			\$80-155M

Table 13: Dakhla Free Zone Fiscal Incentive Comparison (10-Year Projection)

7.3 Energy Regulatory Framework

Morocco's energy regulatory framework for self-production and renewable energy has evolved significantly in recent years. Law 58-15 (2015) authorized the production of electricity from renewable energy sources for self-consumption and authorized the sale of surplus to the ONEE grid under a net billing mechanism. Law 82-21 (2021) further liberalized the market by allowing low-voltage producers to sell directly to consumers. The ANRE (Autorite Nationale de Regulation de l'Electricite) is finalizing the tariff framework for renewable energy transactions, with a comprehensive reform expected by 2027. For the Sahara Neural Hub, the key regulatory considerations are: (1) obtaining the Autoproduction license for the dedicated wind/solar installation (capacity > 20 MW requires ANRE approval); (2) negotiating the PPA/sleeve agreement structure for grid backup power; (3) complying with the grid connection requirements for the 400 kV transmission line; and (4) ensuring that the BESS installation meets the emerging regulations for energy storage systems. The current regulatory trajectory is favorable: Morocco is actively encouraging renewable energy self-production as part of its 52% renewable capacity target by 2030, and the Dakhla-Casablanca transmission line project signals the government's commitment to enabling large-scale renewable energy evacuation from the southern provinces.

7.4 African Union Data Policy Framework

The African Union Data Policy Framework, adopted in February 2024, provides a continental-level governance structure for data that directly supports the Sahara Neural Hub's sovereign data storage proposition. The framework establishes principles for: (1) data governance and sovereignty - recognizing the right of African nations to regulate data within their borders; (2) cross-border data flows - creating a harmonized framework for data transfers between African Union member states; (3) data classification - establishing categories for personal, non-personal, and strategic data; and (4) data infrastructure development - explicitly calling for investment in continental data infrastructure including data centers, cloud platforms, and connectivity. The framework recommends against overly broad data localization mandates that could fragment the continental digital market, while supporting targeted localization for sensitive data categories. This balanced approach is ideal for the Sahara Neural Hub: it creates demand for sovereign African data storage without preventing cross-border services that require data mobility. The facility's compliance with the AU framework will be a competitive advantage, enabling it to serve clients across the continent who need to comply with emerging national data protection laws while still operating at pan-African scale.

8. Risk Analysis

A rigorous risk analysis is essential for any infrastructure investment of this scale. This section identifies and categorizes the key risks across technical, financial, regulatory, geopolitical, and operational dimensions, with specific mitigation strategies for each. The overall risk profile is assessed as Moderate, reflecting the project's strong fundamentals (location, demand, regulatory support) balanced against execution challenges (remote location, emerging regulatory framework, technology volatility).

Risk Category	Risk Description	Probability	Impact	Mitigation Strategy
Geopolitical	Western Sahara sovereignty dispute deters investors	Medium	High	MIGA insurance; legal opinions; EU-Morocco partnership framework
Technical	Renewable energy intermittency causes outages	Medium	High	BESS 4-hour storage; grid backup; 2N UPS; N+1 generators
Financial	GPU pricing volatility exceeds CAPEX budget	High	Medium	Phased procurement; 6-9 month advance orders; B200 migration path
Regulatory	ANRE tariff reform delays energy self-production	Medium	Medium	Early engagement with ANRE; legal reserve; PPA with ONEE
Construction	Logistics delays in remote location	High	Medium	On-site staging; 10% contingency; modular construction approach
Market	Slower-than-expected demand for African GPU compute	Medium	Medium	Anchor tenant pre-commitments; colocation revenue diversification
Operational	Difficulty recruiting skilled staff to Dakhla	Medium	Low	Training center; remote operations; competitive compensation packages
Environmental	Water scarcity competes with local needs	Low	High	DLC cooling (minimal water); desalination; water recycling
Security	Physical or cyber attack on critical infrastructure	Low	Very High	Tier III+ physical security; SOC; ISO 27001; BCP/DRP
Technology	GPU technology obsolescence within 3-5 years	High	Medium	Flexible rack design; GPU refresh cycle; B200/GB200 upgrade path

Table 14: Comprehensive Risk Matrix

9. Project Timeline and Implementation

The Sahara Neural Hub implementation follows a two-phase strategy designed to manage execution risk, optimize capital deployment, and enable market validation before full-scale investment. Phase 1 delivers a 25 MW facility with 1,000 GPUs in 24-36 months, sufficient to establish market presence and generate revenue. Phase 2 expands to 50 MW with 2,000+ GPUs based on market demand validation, with construction overlapping the final months of Phase 1 commissioning. The timeline assumes a greenfield construction approach with parallel workstreams for civil works, power infrastructure, renewable energy installation, and IT systems deployment. Critical path items include: (1) land acquisition and permitting (6-9 months), (2) 400 kV grid connection (12-18 months), (3) wind

farm construction (12-18 months), and (4) GPU server delivery (6-9 months from order, subject to NVIDIA supply constraints). A dedicated project management office (PMO) with monthly milestone tracking and quarterly investor reporting will govern the implementation.




Figure 12: Sahara Neural Hub - Project Implementation Timeline

Phase	Duration	Key Milestones	Investment (\$M)
Pre-Development	Months 0-3	Feasibility, site selection, MoU with DWAFZ	2-5
Design & Permitting	Months 3-9	Engineering design, permits, PPA negotiation	5-15
Procurement	Months 6-14	GPU orders, turbine orders, construction contracts	50-100
Construction Phase 1	Months 9-24	Building, power, cooling, renewable installation	200-400
IT Installation P1	Months 21-27	GPU cluster, network, storage deployment	150-250
Commissioning P1	Months 25-30	Testing, certification, client onboarding	10-20
Phase 1 Go-Live	Month 30	25 MW operational, 1,000 GPUs online	
Phase 2 Expansion	Months 30-48	Second data hall, additional GPUs	200-400
Full Build Go-Live	Month 48	50 MW operational, 2,000+ GPUs online	

Table 15: Implementation Phases and Milestones

10. Organizational Structure and Team

The Sahara Neural Hub requires a multidisciplinary team combining data center operations expertise, AI/ML infrastructure knowledge, renewable energy management, and regulatory compliance capabilities. The organizational structure is designed for lean operations (40 FTE at full capacity) while ensuring 24/7 coverage and rapid incident response. The team will be headquartered in Dakhla with satellite offices in Casablanca (sales and regulatory affairs) and potential European offices (London or Paris for investor relations and client management). Recruitment will prioritize Moroccan talent, supplemented by international specialists for roles requiring rare expertise (GPU cluster operations, InfiniBand network engineering, liquid cooling systems).

Department	Headcount	Key Roles	Annual Cost (\$K)
Executive	3	CEO, CFO, CTO	300-500
Data Center Operations	12	Site manager, shift engineers, technicians	200-350
Network & Systems	8	Network engineers, sysadmins, security	150-250
AI/HPC Operations	5	ML ops, GPU cluster specialists	100-200
Power & Cooling	6	Electrical engineers, HVAC specialists	100-150
Sales & Marketing	4	Sales directors, marketing manager	120-200
Finance & Legal	2	Controller, legal/compliance	60-100
Total	40		1,030-1,750

Table 16: Organizational Structure and Staffing Plan

11. ESG and Sustainability

The Sahara Neural Hub is designed from inception as a net-positive environmental project. Unlike traditional data centers that consume vast amounts of grid electricity and water, this facility will generate more renewable energy than it consumes (surplus exported to the national grid), use minimal water through advanced cooling technologies, and contribute to Morocco's climate commitments under the Paris Agreement. The ESG framework encompasses three pillars: Environmental (100% renewable energy, PUE < 1.20, zero liquid discharge, carbon-negative operations including grid displacement), Social (community benefits agreement, local hiring, training programs, digital inclusion initiatives), and Governance (independent board oversight, regulatory compliance, transparent reporting aligned with TCFD, GRI, and UN SDG frameworks). The project directly contributes to UN Sustainable Development Goals 7 (Affordable and Clean Energy), 8 (Decent Work and Economic Growth), 9 (Industry, Innovation and Infrastructure), 11 (Sustainable Cities), and 13 (Climate Action).

ESG Metric	Target	Industry Benchmark	Status
Power Usage Effectiveness (PUE)	1.10-1.20	1.40-1.60	Target exceeds benchmark by 25%
Carbon Intensity	0 gCO2/kWh (scope 2)	200-500 gCO2/kWh	Net zero through 100% renewables

Water Usage Effectiveness (WUE)	< 0.2 L/kWh	0.8-1.8 L/kWh	DLC + free cooling minimizes water
Renewable Energy Share	100%	20-40%	Dedicated wind + solar + BESS
Waste Heat Recovery	> 30% of waste heat	< 5%	Seawater desalination integration
Local Employment	> 40% of staff	10-20%	Training center + hiring quotas

Table 17: ESG Performance Targets vs. Industry Benchmarks

12. Key Contacts and Partnership Opportunities

Establishing the right partnerships is critical for the Sahara Neural Hub's success. This section identifies key entities across government, energy, telecom, technology, and finance that should be engaged at each stage of the project. Early relationship building, particularly with government agencies and infrastructure providers, can significantly accelerate permitting, grid connection, and site preparation timelines.

Entity	Category	Role	Contact Approach
Agence de Developpement Agricole (ADA)	Government	Land allocation (rural)	Formal application via DWAFZ
MASEN	Government/ Energy	Renewable energy permits, PPA facilitation	Direct engagement, MoU
ANRE	Regulator	Electricity self-production license	Formal license application
CNDP	Regulator	Data protection compliance	Notification + DPO registration
Wali of Dakhla	Government	Regional coordination, fast-track permits	Formal presentation, CBA
ONEE	Utility	Grid connection, power backup	Technical study + connection agreement
Maroc Telecom	Telecom	Submarine cable capacity, fiber	Commercial negotiation
Inwi / Orange Morocco	Telecom	Diverse connectivity paths	Carrier-neutral MMR approach
NVIDIA	Technology	GPU supply, reference architecture	Elite partner program
MIGA / ARI	Insurance	Political risk insurance	Application + premium negotiation
AfDB / IFC	Finance	Project finance, DFI co-investment	Investment committee presentation
Vestas / Siemens Gamesa	Energy	Wind turbine supply, O&M;	Competitive tender process

Table 18: Key Stakeholder Contact Matrix

13. Financing Structure and Capital Strategy

The Sahara Neural Hub's financing strategy leverages a blended capital structure that optimizes cost of capital while managing risk for all parties. The proposed structure consists of: (1) Sponsor Equity (30-40% of total CAPEX, \$180-450M) provided by the project developer and strategic investors, including potential participation from Moroccan sovereign wealth funds (Ithmar Capital) and Gulf investors (PIF, ADIA, Mubadala); (2) Development Finance Institution (DFI) Debt (25-35%, \$150-400M) from the African Development Bank (AfDB), International Finance Corporation (IFC), and European Investment Bank (EIB), providing long-tenor (15-20 year) financing at concessional rates; (3) Commercial Debt (20-30%, \$120-340M) from Moroccan and international banks, secured against the project's assets and revenue streams; and (4) Vendor Financing (5-10%, \$30-115M) from NVIDIA, Vestas, and other equipment suppliers, providing favorable payment terms that reduce upfront CAPEX. The phased investment approach means that Phase 1 requires only \$300-570M, with Phase 2 funded from Phase 1 operating cash flows and additional debt raised after market validation.

Capital Source	Share	Amount (\$M)	Cost of Capital	Tenor
Sponsor Equity	30-40%	180-450	15-18% (IRR target)	Perpetual
DFI Debt (AfDB/IFC/EIB)	25-35%	150-400	4-6% (concessional)	15-20 years
Commercial Bank Debt	20-30%	120-340	6-9% (Moroccan market)	10-15 years
Vendor Financing (NVIDIA, etc.)	5-10%	30-115	3-5% (subsidized)	5-7 years
Green Bonds (future)	10-15%	60-170	4-5% (green premium)	10-15 years

Table 19: Proposed Capital Structure

14. Competitive Positioning and Strategic Moat

The Sahara Neural Hub's competitive moat is built on four interlocking advantages that are extremely difficult for competitors to replicate. First, **location scarcity**: Dakhla's combination of world-class wind resources, operational submarine cable landing, and Free Zone status is unique in Africa. There is no other location on the continent that offers all three simultaneously. Second, **energy cost advantage**: at \$0.022-0.035/kWh, Dakhla's renewable LCOE is 70% below European averages, creating a structural cost advantage that cannot be eroded by competition. Third, **sovereign data positioning**: the facility serves a market (African sovereign data storage) that is driven by regulatory mandates, not discretionary spending, making demand relatively inelastic. Fourth, **first-mover advantage in Dakhla**: as the first data center in the region, the Sahara Neural Hub will establish the ecosystem (connectivity, skills, support services) that makes subsequent competitor entries easier, but will also capture the premium pricing and anchor tenant relationships that come with being first. The primary competitive threats are: (1) the Iozera and Naver Cloud projects in Tetouan, which target the European market from Moroccan soil; (2) emerging data center markets in Nigeria and Kenya; and (3) the remote possibility that satellite connectivity (Starlink, OneWeb) could reduce the connectivity advantage of submarine cable landing points. However, none of these threats directly addresses the sovereign African data storage niche that the Sahara Neural Hub occupies.

15. Appendices

Appendix A: Wind Turbine Specifications

This appendix provides detailed technical specifications for the wind turbine models evaluated for the Sahara Neural Hub renewable energy installation. All models are IEC Class I or II certified for high-wind sites and have proven operational records in similar coastal desert environments. The selection criteria include: capacity factor at the Dakhla wind regime (9.5-10.8 m/s at 80m), levelized cost of energy, turbine availability and warranty terms, local service and maintenance infrastructure, and delivery timeline alignment with the project construction schedule. The Vestas V136-4.5 MW and Siemens Gamesa SG 4.5-145 are the leading candidates based on the combined score of these criteria, with the GE 158-5.5 MW as an alternative for sites where larger rotor diameter provides additional energy capture.

Specification	Vestas V136-4.5	Siemens SG 4.5-145	GE 158-5.5	Enercon E-138 EP3
Rated Power	4.5 MW	4.5 MW	5.5 MW	3.5 MW
Rotor Diameter	136 m	145 m	158 m	138 m
Swept Area	14,527 m ²	16,513 m ²	19,607 m ²	14,993 m ²
Hub Height Options	82 / 112 m	82.5 / 127.5 m	101 / 161 m	81 / 160 m
IEC Class	IEC S (high wind)	IEC I/II	IEC I/II	IEC II
Cut-in Wind Speed	3 m/s	3 m/s	3 m/s	3 m/s
Rated Wind Speed	12 m/s	12 m/s	12.5 m/s	11.5 m/s
Cut-out Wind Speed	25 m/s	25 m/s	25 m/s	25 m/s
Est. Capacity Factor (Dakhla)	45-50%	43-48%	48-53%	40-45%
Estimated Unit Price	\$4.5-6.0M	\$4.5-5.8M	\$5.5-7.0M	\$3.5-4.5M
Delivery Lead Time	12-16 months	14-18 months	16-20 months	12-16 months

Table 20: Wind Turbine Detailed Specifications Comparison

Appendix B: GPU Pricing and Cloud Benchmarks

This appendix provides a comprehensive comparison of GPU hardware pricing and cloud GPU rental rates as of Q1 2025, establishing the revenue floor for the Sahara Neural Hub's GPU-as-a-Service offering. Cloud pricing data is sourced from public AWS, Azure, GCP pricing pages and specialized neo-cloud providers (Lambda Labs, RunPod, Vast.ai, CoreWeave). Hardware pricing reflects distributor and volume discount estimates for 1,000+ unit orders. The key insight is that African GPU compute commands a premium of 15-30% over US/EU pricing due to scarcity and data sovereignty requirements, which supports the revenue projections in Section 5.

Provider / Product	Price per GPU-Hour	GPU Type	Notes
AWS P5.48xlarge (On-Demand)	\$6.88	H100 80GB	8x H100 per instance

AWS P5.48xlarge (1yr Reserved)	\$3.98	H100 80GB	1-year commitment
Azure ND H100 v5 (On-Demand)	\$5.80	H100 80GB	8x H100 per instance
GCP A3 HighGPU (On-Demand)	\$5.40	H100 80GB	8x H100 per instance
Lambda Labs (H100 SXM)	\$2.49	H100 80GB	Bare metal, US only
CoreWeave (H100)	\$2.01-3.44	H100 80GB	Variable by commitment
RunPod (H100)	\$2.49-3.29	H100 80GB	Community cloud
Sahara Neural Hub (Target)	\$2.50-4.50	H100/B200	Sovereign African data

Table 21: GPU Cloud Pricing Benchmarks (Q1 2025)

Appendix C: Key Regulatory Contacts

The following table provides a reference directory of key regulatory and institutional contacts relevant to the Sahara Neural Hub project. All contact information should be verified through official channels before formal engagement. Early pre-consultation meetings are recommended to establish relationships and understand procedural requirements before submitting formal applications.

Institution	Role	Website	Relevance
CNDP	Data Protection Authority	cndp.ma	Data protection compliance, DPO registration
ANRE	Electricity Regulator	anre.ma	Self-production license, grid connection
MASEN	Renewable Energy Agency	masen.ma	Renewable energy permits, PPA facilitation
AMDIE	Investment Promotion	investinmorocco.ma	Investment incentives, fast-track procedures
DWAFZ	Free Zone Authority	dakhla-freezone.ma	Free zone designation, customs exemptions
ONEE	National Utility	one.org.ma	Grid connection, power supply agreement
ANRT	Telecom Regulator	anrt.ma	Telecom licensing, spectrum allocation
Maroc Telecom	Incumbent Operator	iam.ma	Submarine cable capacity, fiber backhaul
Inwi	Telecom Operator	inwi.ma	MEDUSA cable, diverse connectivity
Orange Morocco	Telecom Operator	orange.ma	Alternative fiber, enterprise services

Table 22: Key Regulatory and Institutional Contacts

Appendix D: Assumptions and Methodology

This appendix documents the key assumptions underlying the financial projections, market analysis, and technical specifications presented in this report. All financial projections use a base date of Q1 2025 with all figures in nominal US dollars unless otherwise stated. Exchange rate assumptions: 1 USD = 10 MAD, 1 EUR = 1.08 USD.

Energy cost assumptions: grid electricity at \$0.116/kWh (ONEE HT tariff for industrial users), self-generated wind at \$0.025-0.035/kWh LCOE, BESS at \$0.08-0.12/kWh LCOE. Market size data sourced from Mordor Intelligence, ResearchAndMarkets, and Statista, cross-referenced with Xalam Analytics Africa data center tracker. GPU pricing sourced from public cloud provider pricing pages, distributor quotations, and industry reports (Dell'Oro Group, Tirias Research). Wind resource data sourced from Global Wind Atlas v3.1, IRENA Renewable Energy Statistics 2024, and published academic studies (ScienceDirect, ResearchGate). Construction cost estimates benchmarked against Turner & Townsend International Construction Market Survey 2024, JLL Data Center Cost Index 2024, and comparable project disclosures. All estimates include a +/- 30% accuracy range reflecting the early-stage nature of the project development.